

DIRECTOR GENERAL OF AERONAUTICAL QUALITY ASSURANCE,
MINISTRY OF DEFENCE, NEW DELHI

Central Nodal Officer for the use of test facilities at DGAQA Units	Shri H. V. Heemanth Kumar, Director Phone No. 011-23015211, Fax No. 011-23014914
--	---

TEST FACILITIES AT DGAQA FIELD ESTABLISHMENT

(Charges are inductive only)

Nodal Officer for the use of test facilities at ALISDA, DGAQA, Bangalore			Syed Iftekhhar Ahmed, Director Phone No. 080-23370383, 23379606, Fax No. 080-23379974		
Sl. No.	Test Facilities/ Parameter	Test Equipment & Machine	Range / Accuracy	Hourly Rate in Rs.	Remarks
1	Dust Chamber Mod VSD 120	M/s Vijalakshmi Industries, Bangalore	Dust Concentration: 25 + 5 gms in five min. Temp range: Ambient to + 60°C Temp tolerance: + 3°C	1395+n (835)	Rs 1395 =Labour charge. n = Total no of hours chamber is engaged. Rs 835 =Chamber power charge.
2	Dry Heat Chamber	M/s Kasco Electronics, Pune	Temp range: Ambient to + 300°C Temp tolerance: + 3°C	1395+n (378)	Rs 1395 = Labour charge. n = Total no of hours chamber is engaged. Rs 378 =Chamber power charge.
3	Mould growth Chamber	M/s Kasco Electronics, Pune	Temp range: Ambient to + 20°C to + 60°C RH above 98%, Humidity tolerance: + 3%	1395+n (29 times volume of specimen)	Rs 1395 = Labour charge. n = Total no of hours chamber is engaged.
4	Salt Spray Chamber 'L' type	M/s Consolidated Electric Industries, Bangalore	Temp range: Ambient to + 70°C Humidity : up to 95%	1395+n (362)	Rs 1395 = Labour charge. n = Total no of hours chamber is engaged. Rs 362 =Chamber power charge.

Nodal Officer for the use of test facilities at OAQA, DGAQA, Dehradun			Shri N K Dua, P.Sc.O. Phone NO. 0135-2787145, Fax NO. 0135-2787090		
Sl. No.	Test Facilities/ Parameter	Test Equipment & Machine	Range / Accuracy	Hourly Rate in Rs.	Remarks
1	Hot set test, Hot deformation testing of cables	M/s S. A. Associates, Delhi	Ambient to 300 \pm 5C	Rs.750.00	
2	Hi voltage AC Tester for cables (0-25 KV)	M/s Automatic Electric Ltd. Bombay	0-25 KV	Rs.700.00	